

Organic laying hen stall made of Swiss wood

Willerzell, CH



Organic laying hen stall made of Swiss wood

Willerzell, CH



Project details

Client	Private
Architecture	Plan-Werk.ch GmbH
Project type	Agriculture construction
Construction type	Wood element construction
Services	Timber construction
Own products	Fassaden
Construction	2016, 2017
Locality	Willerzell
Country	Switzerland

info@blumer-lehmann.com
blumer-lehmann.com

The fascinating world of wood

Organic laying hen stall made of Swiss wood

Willerzell, CH



Agricultural timber construction

The timber supporting structure for the organic laying hen stall concept for hosberg ag – which includes an anteroom and lounge – is based on a supported girder design. The flexibility of the timber construction enabled the building to be precisely adapted to on-site conditions. The laminated purlins installed perpendicular to the roof pitch form the secondary supporting structure.

The static dimensions for the timber supporting structure as well as the design plans and working drawings were prepared by the engineers at Blumer-Lehmann AG. The CNC-processed timber structural elements and prefabricated wood elements will be delivered to the site ready for assembly and assembled within a few days. The walls were clad with prefabricated, insulated wood elements. Thanks to the Swiss timber facade, the building blends seamlessly into the surroundings. The roof was clad with sandwich panels.

Specific Contact



Hansueli Frei

Sales Agricultural Buildings | Timber
Construction | Switzerland

T +41 71 388 51 68

hansueli.frei@blumer-lehmann.com

Organic laying hen stall made of Swiss wood

Willerzell, CH




Front side with spruce/pine cladding



Plenty of daylight inside the coop

Organic laying hen stall made of Swiss wood

Willerzell, CH



A comfortable coop for organically reared laying hens

Fresh air in the free-range enclosure