

Production hall and offices in timber construction

Steinau an der Straße, DE



Project details

Client	Blumer-Lehmann AG
Architecture	baut architektur partmbb
Project type	Commercial and industrial
Construction type	Wood element construction
Services	General contractor services (GC)
Construction	2024-2026
Locality	Steinau an der Straße
Country	Germany

New building for more production capacity

The modular, expandable production hall with an area of 5400 m² will house element and module production as well as storage and logistics. The actual production area is 27 m wide and constructed without columns. The building is designed as a timber frame structure. Optimised prefabrication was the focus for the facade design. The facade slats are therefore already installed horizontally or vertically during element production.

The office wing, made of seven of our own second-life timber modules, is a separate building on the site. The site uses a heat pump and a photovoltaic system for its energy supply.

The company premises, located on a greenfield site, gave the team the unusual task of first having the ground inspected and then incorporating the nesting and breeding seasons of the wild animals into the project planning.

Specific Contact



Lukas Osterwalder

Division Manager Timber and Modular
Construction | DE | AT | LU

Member of the Executive Board

T +41 71 388 58 20

lukas.osterwalder@blumer-lehmann.com