

Temporary school premises for Stadelhofen Cantonal School

Dübendorf, CH



Project details

Client	Bildungsdirektion Kanton Zürich
Architecture	Bauart Architekten und Planer AG, pool Architekten, UNIT Architekten AG
Project type	Education and research
Construction type	Modular construction
Services	JC
Construction	2024-2026
Locality	Dübendorf
Country	Switzerland

Temporary secondary school

After the planned initial usage period of nine years, the modular timber and element-based constructions are to be dismantled and reused at another location. The temporary secondary school will consist of two three-storey classroom buildings connected by an open intermediate structure, plus a sports hall wing with two single halls. The two school wings with a total area of 7800 m² are composed of 246 timber modules. Three modules together form a 69 m² classroom.

The facades are structured in line with the modular design. Vertical timber structures and transparent lightweight corrugated panels give the sports hall a bright, temporary character. In the school wings, vertical, rough-cut wooden slats interact with the lightweight corrugated panels in the sports hall. Each part of the building will have its own colour.

The construction project will be built in accordance with the "Standard Nachhaltigkeit Hochbau" (sustainability construction standard). The school wings and the construction and building services of the sports wing meet the Minergie-Eco standard. Heating and cooling are generated by air-to-water heat pumps. The roof areas will be extensively planted with greenery and equipped with a photovoltaic system.

Specific Contact



Migga Hug

Head of GC & TC Services |
Architectural planning | Switzerland
Member of the Division Management

T +41 71 388 58 23
migga.hug@blumer-lehmann.com